


KEY

N - noggin, see drawing 1007-32 for detail

3 no. ventilation holes

Reclaimed sheets of plywood				
	W	L	D	Qty
A	2210	1220	12	2
B	2170	1050	12	1
C	1390	1210	12	1
D	1390	1060	12	1





Noggin elevation (N) 1:10

Plywood fixing

- Lay panels with the face grain parallel to the span
- Support all short edges on a joist and stagger end joints
- Support the perimeter of the roof continuously on timber members
- Use galvanised flat head nails, or countersunk screws, 2.5 times the panel thickness, i.e. 30mm
- Space fixings at 400mm centres to each supporting timber and not less than 10mm from the panel edge
- Protect panels from wet weather until covered with weatherproof finish

Plywood requirements

8 no. 2440x1220x12 square
edged roofing grade plywood



Steven Coulsting Architect
4 Crackley Cottages, Coventry Road
Kenilworth CV8 2FG
Tel 01926 858895
Email stevenc@eco-architects.org

Tian Coulsting
127 Whitecroft Road workshop
Roof deck layout

Scale: 1:25@A3
Date: Aug 2016
Drg no. **1007 / 31D**

Date: Aug 2016

Drg no. **1007 / 31D**